



Invitation to Tender for the Construction of Ufayn Road Rehabilitation

Issuer	Ufayn Road committee- Ufayn
Release date	25.10.2021
Supplier Response Date	30.10.2021
Delivery Date	05.10.2021
Delivery location	Ufayn, Puntland, Somalia
Delivery days	5 days

Invitation to Tender for Road Rehabilitation- Ufayn district

Dear Vendors

You are invited to submit a tender to Rehabilitate Ufayn Road to Ufayn community project implementation unit. By participating in this tender, you are indicating your acceptance to be bound by the requirements and specifications set out in this letter and attachments. We provide below the key details of *tender* requirements and we strictly follow exact specifications, which you should consider in your response.

- **Detailed Quotation including**
- **Legal registration certificate if you're in Puntland/Somalia**
- **Construction license**
- **Brief company profile**

Specification of the BOQ in a table form

Rehabilitation of Portion of Ufayn Feeder Road.

Please bring your expression of interest to be considered as an applicant of the tender. We encourage all interested suppliers to meet the deadline.

Contacts tell 0907791192/7792049
Email:Midnimocharity203@gmail.com

CARE SOMALIA/ SOMALILAND

PROJECT : CROWFUNDING PROJECTS

DISTRICT: Bosaso District

TOWN : UFAYN

BOQ of Rehabilitation of Ufayn Feeder Road from Bosaso to Ufayn Town (6km long)

SN	DESCRIPTION	UNIT	QUANTITY	RATE IN USD	AMOUNT IN USD
Dimension of portion of the Ufayn Feeder Road : 8m wide x 6km long					
A	1-Earth Work				
1	Clearing of the road bed in removing top vegetative soil , debris and trees to an average depth of 10cm .	M ²	48.00		
2	Settingg out the alignmets of the feeder Road through using surveying instrument or equivalent tools applying the skilled surveyor of road Engnieer before commence any earth work. All bench marks should be clearly established by the surveyor.	M ²	48.00		
3	Carry out road rehabilitation through applying machinery -based labour (Cartipliar machine) with actual dimensions of 8m wide and 6km long long in carryingg out the fill and cutt process , levelling andcompaction of the road to depth of 50cm .	LM	6000.00		
4	Curing on water fo the levelled and comapcted road which is the final finishing works of the road .	M ³	35.00		
5	Hiring two skilled labosurs (one skilled for man , Road Enginner and One surveyor for measuring road aligments (15 days x 2 persons x30 USD)	Persons	30.00		
Grand Total					-

CARE SOMALIA/SOMALILAND

EU-RESTORE PROJECT

TOTAL SUMMARY CARRIED OUT FROM BOQS OF UFAYN FEEDER ROAD IN UFAYN TOWN ,BARI REGION , EU-RESTORE PROJECT.

Sn	Description	Units	Qunatity	Rate in US\$	Amount in USD
1	Rehabilitation of Portion of Ufayn Feeder Road (8m wide and 6km long) in Ufayn Town ,Bosaso District , Bari Region .	No	1		
Grand Total					